

Wykaz przepustów

Tablica 1.4

Pikietaż	Rów lewy	Rów prawy	Ciek wodny
0 + 346,56	7,0 m Ø300	-	-
0 + 347,70	-	6,5 m Ø300	-
0 + 663,42	-	6,5 m Ø300	-
0 + 676,64	8,5 m Ø300	-	-
0 + 701,52	-	-	7,5; 2,5 m Ø600
1 + 363,43	-	-	7,0 m Ø600
1 + 837,34	-	7,0 m Ø300	-
1 + 964,96	-	-	9,0 m Ø600
2 + 097,63	-	-	7,5 m Ø600
2 + 233,11	-	-	8,5 m Ø600
2 + 290,75	-	-	7,0 m Ø600
2 + 495,00	-	-	11,5 m Ø600
2 + 658,06	-	7,0 m Ø300	
2 + 771,77	-	-	8,5 Ø600
2 + 908,99	-	-	8,5 Ø1000